



B2W Software, Inc.  
 Martingale Wharf  
 99 Bow Street, Suite 500  
 Portsmouth, NH 03801

## SAMPLE REPORT

### Crew Component Listing

<b>Project Name:</b> Fox Hill Economic Development Project	<b>Customer:</b> Agneron Construction
<b>Job Number:</b> 100 <b>Bid Number:</b> 6546874	<b>Billing Address:</b> 45 Bushmills Rd.
<b>Bid As:</b> General Contractor	Jupiter, FL
<b>Estimator:</b> Tom Willey	<b>Phone:</b> (863) 555-9032
<b>Project Address:</b> 100 Cross Road, Chichester, NH	<b>Contact:</b> Jim Agner
<b>Completion Date:</b> 4/30/2019	

### Crew Component Listing

Crew Name	Description	Rate	Method	Days	Quantity	UM	Unit Cost	Total Cost
Excavation Crew	100 - Common Excavation	675.00	CY/DY	9.78	6,600.00	CY	\$9.66	\$63,782.02
Excavation Crew	180 - Install 18" RCP	850.00	CY/DY	10.59	9,000.00	CY	\$4.90	\$44,099.36
Excavation Crew	30 - Common Excavation	765.00	CY/DY	11.76	9,000.00	CY	\$5.44	\$48,999.29
Excavation Crew	40 - Stabilize Embankment	680.00	CY/DY	9.71	6,600.00	CY	\$6.12	\$40,424.42
Excavation Crew	40 - Stabilize Embankment	800.00	TON/DY	6.25	5,000.00	TON	\$5.21	\$26,030.87
Fine Grading Crew	50 - Fine Grading	504.00	SY/DY	89.29	45,000.00	SY	\$7.99	\$359,695.18
Highway Paving Crew	225 - 1" Asphalt Paving	720.00	TON/DY	4.95	3,564.00	TON	\$8.00	\$28,494.83
Highway Paving Crew	230 - 2" Asphalt Paving	720.00	TON/DY	8.86	6,380.00	TON	\$9.63	\$61,455.80
Hydro Seeding	230 - 2" Asphalt Paving	1,350.00	SY/DY	42.96	58,000.00	SY	\$1.08	\$62,643.56
Mobilization Crew	10 - Mobilization	1.80	EACH/DY	11.11	20.00	EACH	\$782.61	\$15,652.29
Pipe Crew, Standard	180 - Install 18" RCP	90.00	LF/DY	25.00	2,250.00	LF	\$37.47	\$84,302.80
Pipe Crew, Standard	220 - Furnish And Install 36" RCP	72.00	LF/DY	12.85	925.00	LF	\$46.83	\$43,322.27
							243.10	\$878,902.70