



B2W Software, Inc.
 Martingale Wharf
 99 Bow Street, Suite 500
 Portsmouth, NH 03801

SAMPLE REPORT


























Task Template Resource Detail



























16" Shoes	Quantity: 0.00 EACH	Category: Shoes Categorize As: Subcontracted	Work Type: Pipe	Unit Cost: \$800.00
3" Asphalt Paving	Sample Qty: 6,000.00 SY	Category: Private	Work Type: Paving	
2" Base Course	Quantity: 0.11 x Parent Qty.	Sample Qty: 660.00 TON	Work Type: Paving	
Road Paving Crew	Quantity: 1 x Parent Qty.	Sample Qty: 660.00 TON	Production Rate: 150.00 TON/PH [†]	
Asphalt Base	Quantity: 1 x Parent Qty.	Sample Qty: 660.00 TON		
Trucking	Quantity: 1 x Parent Qty. Job Cost ID: 1000	Sample Qty: 660.00 TON	Round Trip: 1.50 HR Capacity: 22.00 TON	Cost per Hour: \$52.00
1" Surface Course	Quantity: 0.055 x Parent Qty.	Sample Qty: 330.00 TON	Work Type: Paving	
Road Paving Crew	Quantity: 1 x Parent Qty.	Sample Qty: 330.00 TON	Production Rate: 150.00 TON/PH [†]	
Asphalt Surface	Quantity: 1 x Parent Qty.	Sample Qty: 330.00 TON		
Trucking	Quantity: 1 x Parent Qty. Job Cost ID: 1000	Sample Qty: 330.00 TON	Round Trip: 1.00 HR Capacity: 22.00 TON	Cost per Hour: \$52.00
6" Extruded Curb	Quantity: 0.00 LF	Categorize As: Subcontracted	Work Type: Concrete	Unit Cost: \$17.25
Backfill	Sample Qty: 16,916.00 CY Job Cost ID: 1600		Work Type: Earthwork	
Excavation Crew	Quantity: 1 x Parent Qty.	Sample Qty: 16,916.00 CY	Production Rate: 850.00 CY/DY [†]	
Bridge	Sample Qty: 1.00 LS	Category: Public	Work Type: Bridge	
Ballast	Quantity: 0.00 CY	Sample Qty: 0.00 CY	Work Type: Bridge	
Structure Excavation	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 CY	Work Type: Bridge	
Structure Excavation Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 CY	Production Rate: 225.00 CY/DY [†]	





























(Task Template Bridge Continued)

 Ballast	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 CY	
 Cement Treated Backfill	Quantity: 0.00 LS	Sample Qty: 0.00 LS	Work Type: Bridge
 Structure Excavation Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LS	Production Rate: 0.00 LS/DY ⁺
 Form Walls	Quantity: 0.00 SF	Sample Qty: 0.00 SF	Work Type: Bridge
 Form Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 SF	Production Rate: 0.00 SF/DY ⁺
 Form Lumber, PT 2 X 10	Quantity: 0.00 LF	Sample Qty: 0.00 LF	
 Metal Deck Superstructure	Quantity: 0.00 SF	Sample Qty: 0.00 SF	Work Type: Bridge
 Form Drop Downs At Piers	Quantity: 0.00 LF	Sample Qty: 0.00 LF	Work Type: Bridge
 Form Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF	Production Rate: 0.50 MH/LF
 Form Lumber, PT 2 X 10	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF	
 Form Fascia	Quantity: 0.00 LF	Sample Qty: 0.00 LF	Work Type: Bridge
 Form Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF	Production Rate: 0.50 MH/LF ⁺
 Form Lumber, PT 2 X 10	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF	
 Form Deck	Quantity: 0.00 TF	Sample Qty: 0.00 TF	Work Type: Bridge
 Form Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 TF	Production Rate: 0.00 TF/DY ⁺
 Form Deck Styrofoam	Quantity: 0.00 SF	Sample Qty: 0.00 SF	
 Metal Deck Form Materials	Quantity: 0.00 SF	Sample Qty: 0.00 SF	
 Form Longitudinal Bulkhead	Quantity: 0.00 LF	Sample Qty: 0.00 LF	Work Type: Bridge
 Aggregate Base Placement Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF	Production Rate: 0.00 LF/DY ⁺
 Aggregate (road Spec) 3/8in	Quantity: 0.00 TON	Sample Qty: 0.00 TON	
 Form Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF	Production Rate: 0.50 MH/LF ⁺
 2 X 4 Lay In Troffer	Quantity: 0.00 EACH	Sample Qty: 0.00 EACH	
 Form Lumber, PT 2 X 10	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF	
 Strip	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 SF	Work Type: Bridge
 Deck Stripping Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 SF	Production Rate: 200.00 SF/PH ⁺
 Pour Deck	Quantity: 0.00 SY	Sample Qty: 0.00 SY	Work Type: Bridge
 Pour Substructure Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 SY	Production Rate: 0.00 SY/DY ⁺
 Cure - Interim	Quantity: 0.00 GAL	Sample Qty: 0.00 GAL	
 Form Traverse Bulkhead	Quantity: 0.00 LF	Sample Qty: 0.00 LF	Work Type: Bridge
 Form Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF	Production Rate: 0.50 MH/LF ⁺
 Form Lumber, PT 2 X 10	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF	
 Pour Walls & Footings	Quantity: 0.00 CY	Sample Qty: 0.00 CY	Work Type: Bridge
 Pour Substructure Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 CY	Production Rate: 0.00 CY/DY ⁺





(Task Template Bridge Continued)


 Class AA Concrete	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 CY		
 Form Footing	Quantity: 0.00 LF	Sample Qty: 0.00 LF	Work Type: Bridge	
 Form Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF	Production Rate: 0.50 MH/LF ⁺	
 Form Lumber, PT 2 X 10	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF		
<hr/>				
 Clearing Site	Sample Qty: 0.00 ACRE		Work Type: Clearing & Grubbing	
 Clearing Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 ACRE	Production Rate: 3.00 ACRE/DY ⁺	
 Haul Stumps	Quantity: 1.00 LS	Sample Qty: 1.00 LS	Work Type: Clearing & Grubbing	Unit Cost: \$4,000.00
	<u>Cost Category</u> Trucking Owned	<u>Unit Cost</u> \$4,000.00		
<hr/>				
 Concrete For Apron	Sample Qty: 0.00 CY		Work Type: Concrete	
 Concrete Pour Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 CY	Production Rate: 50.00 CY/DY ⁺	
 Concrete	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 CY		
<hr/>				
 Concrete Paving (Reinforced)	Sample Qty: 1,000.00 CY		Work Type: Concrete	
 Concrete Paving Crew	Quantity: 1 x Parent Qty.	Sample Qty: 1,000.00 CY	Production Rate: 5.00 CY/MH ⁺	
 Class A Concrete	Quantity: 1 x Parent Qty.	Sample Qty: 1,000.00 CY		
 Rebar	Quantity: 30 x Parent Qty.	Sample Qty: 30,000.00 LB		
 Trucking	Quantity: 1,000.00 CY	Sample Qty: 1,000.00 CY	Round Trip: 0.00 HR Capacity: 12.00 CY	Cost per Hour: \$88.00
<hr/>				
 Concrete Paving, Class A	Sample Qty: 5,000.00 CY Job Cost ID: 1200		Work Type: Concrete	
 Concrete Paving Crew	Quantity: 1 x Parent Qty.	Sample Qty: 5,000.00 CY	Production Rate: 500.00 CY/DY	
 Class A Concrete	Quantity: 1 x Parent Qty.	Sample Qty: 5,000.00 CY		
 Trucking	Quantity: 5,000.00 CY	Sample Qty: 5,000.00 CY	Round Trip: 1.00 HR Capacity: 12.00 CY	Cost per Hour: \$88.00
<hr/>				
 Concrete Paving, Class AA	Sample Qty: 5,000.00 CY		Work Type: Concrete	
 Concrete Paving Crew	Quantity: 1 x Parent Qty.	Sample Qty: 5,000.00 CY	Production Rate: 500.00 CY/DY	
 Class AA Concrete	Quantity: 1 x Parent Qty.	Sample Qty: 5,000.00 CY		
<hr/>				
 Crushed Gravel Install	Sample Qty: 0.00 CY			
 Two Man Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 CY	Production Rate: 15.00 CY/PH	
 Crushed Gravel (CY)	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 CY		
<hr/>				
 Drilling Mud	Sample Qty: 1,000.00 GAL			



 Bentonite	Quantity: 0.25 x Parent Qty.	Sample Qty: 250.00 GAL		
 Water	Quantity: 0.75 x Parent Qty.	Sample Qty: 750.00 GAL		
 Excavate Trench	Sample Qty: 18,370.00 CY Job Cost ID: 1800		Work Type: Excavation	
 Excavation Crew	Quantity: 1 x Parent Qty.	Sample Qty: 18,370.00 CY	Production Rate: 850.00 CY/DY ⁺	
 Excavation	Sample Qty: 1,000.00 CY Job Cost ID: 1800	Category: Private	Work Type: Excavation	
 Excavation Crew	Quantity: 1 x Parent Qty.	Sample Qty: 1,000.00 CY	Production Rate: 850.00 CY/DY ⁺	
 Trucking	Quantity: 1 x Parent Qty. Job Cost ID: 1000	Sample Qty: 1,000.00 CY	Round Trip: 0.00 HR Capacity: 12.00 CY	Cost per Hour: \$88.00
 Fill Shaft	Sample Qty: 0.00 CY		Work Type: Concrete	
 Concrete Pour Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 CY	Production Rate: 50.00 CY/DY ⁺	
 Class A Concrete	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 CY		
 Fine Grading	Sample Qty: 20,000.00 SY	Category: Private	Work Type: Grading	
 Fine Grading Crew	Quantity: 1 x Parent Qty.	Sample Qty: 20,000.00 SY	Production Rate: 2,000.00 SY/DY ⁺	
 Forming Material For Apron	Sample Qty: 0.00 SF		Work Type: Concrete	
 Two Man Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 SF	Production Rate: 10.00 SF/PH	
 Forming Material	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 SF		
 Ground Wire Placement	Sample Qty: 0.00 LF		Work Type: Electrical	
 Wiring Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF	Production Rate: 0.00 LF/DY ⁺	
 High Tension Tower	Sample Qty: 1.00 EACH		Work Type: Electrical	
 Steel/Iron Crew	Quantity: 1 x Parent Qty.	Sample Qty: 1.00 EACH	Production Rate: 2.00 DY/EACH	
 Structural Steel	Quantity: 12000 x Parent Qty.	Sample Qty: 12,000.00 LB		
 Pole/Tower Foundation	Quantity: 16 x Parent Qty.	Sample Qty: 16.00 CY		
 Highway Paving With Night Paving	Sample Qty: 30,000.00 TON	Category: Public	Work Type: Paving	
 Mainline	Quantity: 0.75 x Parent Qty.	Sample Qty: 22,500.00 TON	Work Type: Paving	
 Ramps	Quantity: 0.25 x Parent Qty.	Sample Qty: 7,500.00 TON	Work Type: Paving	
 Install 12" Water Line	Sample Qty: 0.00 LF Job Cost ID: 2400		Work Type: Waterline	
 Pipe Crew, Standard	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF	Production Rate: 200.00 LF/DY ⁺	




 Pipe, PVC 12"	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF		
 Bedding 3/4"	Quantity: 0.125 x Parent Qty.	Sample Qty: 0.00 TON		
 Install 6" Water Line	Sample Qty: 0.00 LF Job Cost ID: 2400		Work Type: Waterline	
 Pipe Crew, Standard	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF	Production Rate: 200.00 LF/DY ⁺	
 Pipe, PVC 06"	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF		
 Bedding 3/4"	Quantity: 0.2 x Parent Qty.	Sample Qty: 0.00 TON		
 Install Pipe	Sample Qty: 8,000.00 LF Job Cost ID: 2400		Work Type: Pipe	
 Pipe Crew, Standard	Quantity: 1 x Parent Qty.	Sample Qty: 8,000.00 LF	Production Rate: 200.00 LF/DY ⁺	
 Pipe, RCP, 18"	Quantity: 1 x Parent Qty.	Sample Qty: 8,000.00 LF		
 Pipe Bedding	Quantity: Value from workbook	Sample Qty: 340.80 CY		
 Silt Fence	Quantity: 1 x Parent Qty.	Sample Qty: 8,000.00 LF		
 Install Powerline, High Tension, 8 Strand	Sample Qty: 0.00 LF		Work Type: Electrical	
 Overhead Electrical Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF	Production Rate: 20.00 LF/MH ⁺	
 High Tension Power Line	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF		
 Conductor	Quantity: 0.005 x Parent Qty.	Sample Qty: 0.00 EACH		
 Mainline	Sample Qty: 0.00 TON		Work Type: Paving	
 Night	Quantity: 0.8 x Parent Qty.	Sample Qty: 0.00 TON	Work Type: Paving	
 Highway Paving Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 TON	Production Rate: 1,000.00 TON/DY ⁺	
 Asphalt Surface	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 TON		
 Trucking	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 TON	Round Trip: 1.50 HR Capacity: 22.00 TON	Cost per Hour: \$52.00
 Lighting	Quantity: 1.00 LS	Sample Qty: 1.00 LS	Work Type: Paving	
 Day	Quantity: 0.2 x Parent Qty.	Sample Qty: 0.00 TON	Work Type: Paving	
 Highway Paving Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 TON	Production Rate: 1,000.00 TON/DY ⁺	
 Asphalt Surface	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 TON		
 Trucking	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 TON	Round Trip: 1.00 HR Capacity: 22.00 TON	Cost per Hour: \$52.00
 Mast Arm, Steel (20 Feet)	Sample Qty: 5.00 EACH		Work Type: Electrical	
 Bucket Truck Crew	Quantity: 1 x Parent Qty.	Sample Qty: 5.00 EACH	Production Rate: 2.00 EACH/DY ⁺	
 Coupling, Steel	Quantity: 4 x Parent Qty.	Sample Qty: 20.00 EACH		





(Task Template Mast Arm, Steel (20 Feet) Continued)

 Elbow, 90 Degree, Steel	Quantity: 2 x Parent Qty.	Sample Qty: 10.00 EACH
 Pole, Steel 4" X 20'	Quantity: 1 x Parent Qty.	Sample Qty: 5.00 EACH
 Mast Arm - Double	Quantity: 1 x Parent Qty.	Sample Qty: 5.00 EACH
 Conduit, PVC SCH 80, 2.0"	Quantity: 50.00 LF	Sample Qty: 50.00 LF

 Milling	Sample Qty: 0.00 TON	Work Type: Asphalt	Unit Cost: \$20.00
	Cost Category	Unit Cost	
	Equipment Owned	\$6.00	
	Labor	\$12.00	
	Materials Purchased	\$2.00	

 Milling By The Ton	Sample Qty: 0.00 TON			
 Milling Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 TON	Production Rate: 250.00 TON/DY ⁺	
 Trucking	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 TON	Round Trip: 0.00 HR	Cost per Hour: \$88.00
			Capacity: 15.00 TON	

 Overhead Lines	Sample Qty: 0.00 LF			
 Overhead Electrical Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF	Production Rate: 20.00 LF/MH ⁺	
 Overhead Ground Wire Assembly	Quantity: 0.00 EACH	Sample Qty: 0.00 EACH		


























 Paving By The Ton	Sample Qty: 3,500.00 TON		Work Type: Paving	
	Job Cost ID: 2300			
 Highway Paving Crew	Quantity: 1 x Parent Qty.	Sample Qty: 3,500.00 TON	Production Rate: 1,000.00 TON/DY ⁺	
 Asphalt Base	Quantity: 1 x Parent Qty.	Sample Qty: 3,500.00 TON		
 Trucking	Quantity: 3,500.00 TON	Sample Qty: 3,500.00 TON	Round Trip: 0.00 HR	Cost per Hour: \$88.00
			Capacity: 15.00 TON	

 Paving By The Ton PG-64-22	Sample Qty: 0.00 TON		Work Type: Paving	
 Highway Paving Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 TON	Production Rate: 120.00 TON/PH	
 Asphalt Base, PG-64-22	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 TON		
 Trucking	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 TON	Round Trip: 0.00 HR	Cost per Hour: \$85.00
	Job Cost ID: 1000		Capacity: 13.00 TON	

 Pole/Tower Foundation	Sample Qty: 0.00 CY			
 Concrete Pour Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 CY	Production Rate: 200.00 CY/DY	
 Class A Concrete	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 CY		

 Primary Lines	Sample Qty: 0.00 LF		Work Type: Electrical	
--	----------------------------	--	------------------------------	--

(Task Template Primary Lines Continued)

 Wiring Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 LF	Production Rate: 0.00 LF/DY [†]	
 Wire, Overhead Electrical	Quantity: 8 x Parent Qty.	Sample Qty: 0.00 LF		
 Conductor	Quantity: 0.032 x Parent Qty.	Sample Qty: 0.00 EACH		
 Insulator	Quantity: 0.00 EACH	Sample Qty: 0.00 EACH		
<hr/>				
 Ramps	Sample Qty: 0.00 TON		Work Type: Paving	
 Hand Paving Crew	Quantity: 0.1 x Parent Qty.	Sample Qty: 0.00 TON	Production Rate: 75.00 TON/PH [†]	
 Highway Paving Crew	Quantity: 0.9 x Parent Qty.	Sample Qty: 0.00 TON	Production Rate: 1,000.00 TON/DY [†]	
 Asphalt Surface	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 TON		
 Trucking	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 TON	Round Trip: 1.00 HR	Cost per Hour: \$52.00
	Job Cost ID: 1000		Capacity: 22.00 TON	
<hr/>				
 Remove Asbestos	Sample Qty: 0.00 SF		Work Type: Remediation	
 Asbestos Abatement Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 SF	Production Rate: 500.00 SF/DY [†]	
<hr/>				
 Roadway Resurfacing	Sample Qty: 20,000.00 TON	Category: Public	Work Type: Paving	
 Hand Paving Crew	Quantity: 0.1 x Parent Qty.	Sample Qty: 2,000.00 TON	Production Rate: 50.00 TON/PH	
 Highway Paving Crew	Quantity: 0.9 x Parent Qty.	Sample Qty: 18,000.00 TON	Production Rate: 125.00 TON/PH	
 Asphalt Surface	Quantity: 1 x Parent Qty.	Sample Qty: 20,000.00 TON		
 Trucking	Quantity: 1 x Parent Qty.	Sample Qty: 20,000.00 TON	Round Trip: 1.00 HR	Cost per Hour: \$52.00
	Job Cost ID: 1000		Capacity: 22.00 TON	
 Tack	Quantity: 0.025 x Parent Qty.	Sample Qty: 500.00 GAL	Work Type: Paving	Unit Cost: \$1.00
		Categorize As: Subcontracted		
 Sweeping	Quantity: 1.00 LS	Sample Qty: 1.00 LS	Work Type: Sweeping	Unit Cost: \$2,000.00
		Categorize As: Subcontracted		
<hr/>				
 Sweeping	Quantity: 1.00 HR	Category: Private	Work Type: Sweeping	Unit Cost: \$150.00
		Categorize As: Subcontracted		
<hr/>				
 Transformer	Sample Qty: 0.00 EACH			
 Two Man Electrical Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 EACH	Production Rate: 3.00 EACH/DY	
 Transformer, Window Type	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 EACH		
<hr/>				
 Transformer Pad	Sample Qty: 0.00 EACH		Work Type: Concrete	
 Concrete Pour Crew	Quantity: 1 x Parent Qty.	Sample Qty: 0.00 EACH	Production Rate: 1.00 EACH/DY	
 Class A Concrete	Quantity: 5 x Parent Qty.	Sample Qty: 0.00 CY		

 **Video Inspection**

Quantity: 0.00 LF

Categorize As: Subcontracted

Work Type: Testing

Unit Cost: \$2.25
